

DARSWEIL L. ROGERS, COMMISSIONER
WADE R. FOWLER, JR., COMMISSIONER
EVELYN O. SHAW, COMMISSIONER
D. RALPH HUFF, III, COMMISSIONER
ELAINA L. BALL, CEO/GENERAL MANAGER



FAYETTEVILLE PUBLIC WORKS COMMISSION
955 OLD WILMINGTON RD
P.O. BOX 1089
FAYETTEVILLE, NORTH CAROLINA 28302-1089
TELEPHONE (910) 483-1401
WWW.FAYPWC.COM

October 14, 2021

TO: All Prospective Bidders

FROM: Trent Ensley, Procurement Manager

SUBJECT: ADDENDUM NO. 1
PWC2122019 – BLACK AND DECKER SUBSTATION
REBUILD INSTALLATION LABOR CONTRACT

1. The Specifications and Bid Documents are hereby modified or clarified per the attached documents.
2. The foregoing changes or clarifications shall be incorporated in the original Bid Documents and a signed copy of this Addendum No. 1 shall accompany the bid to acknowledge the bidder's receipt and familiarity with the changes and/or clarifications.

TE:tke

Acknowledgement:

Company_____

By_____

Date_____

ADDENDUM NO.1
October 14, 2021

FAYETTEVILLE PUBLIC WORKS COMMISSION

PWC2122019

**BLACK AND DECKER SUBSTATION REBUILD INSTALLATION LABOR
CONTRACT**

The following are the questions received today from the pre-bid meeting and the response:

1. Fence replacement details and specifications?

Answer: The sections of fence that adjacent the houses and along the back of the yard will be replaced per the attached specifications. The section along the houses is approximately 375 feet and the section on the backside of the yard is approximately 204 feet. Also, where the two sheds are will need to have fence installed once the sheds are removed.

2. Old substation equipment disposal?

Answer: The contractor will be responsible of disposal of all old equipment and substation steel minus the transformer, regulators and capacitor bank.

3. Control house foundation release?

Answer: The drawing for the control house is accurate and is good for construction.

4. Old foundation specifications?

Answer: I cannot find a drawing but do have old records to show the breaker pads are 4X6X2, the regulator pad is 12X16X2, transformer pad 12X15X2, and control house 10X20X2.

5. Replace wood camera poles with fiberglass?

Answer: We will replace the wood security poles that houses our cameras with fiberglass poles provided by PWC.